Due Fili Plus video door entry systems



7200 series - video door entry units

7200 series video door entry unit

Two-channel hands-free video door entry unit. Thermoplastic cover. High-resolution monitor with 7" TFT LCD colour screen, 16:9 widescreen aspect ratio and loudspeaker for electronic call. Equipped with 8 backlit buttons for: door lock release, self-start, auxiliary services (stair light), intercom calls, talk, internal voice line volume control, ringtone volume control and mute, selection of different ringtones, brightness control and removable terminal block. Dedicated door-open and ringtone mute indicators. Monitor customizable with interchangeable covers.

Conformity to standards **EMC** Directive

Main specifications

- Power supply: Due Fili Plus two-wire Bus.
- Input for additional power supply (6923), allowing simultaneous start-up of more than two internal units.
- 7" TFT LCD display, 16:9 widescreen aspect ratio.
- ABS thermoplastic cover.
- Keypad with 8 backlit buttons.

- Removable terminal block for connection to system.
- Electronic ringtone.
- Input for landing call with ringtone sound different from entrance panel and intercom ringtone.
- Output for additional ringtone 860A or relay 0170/101.
- Flush wall mount and desk-top installation.
- Option of choosing between hands-free communication mode, with no need to keep the talk/listen button pressed, or conventional mode, pressing and holding the talk/listen button.
- Dimensions: 193x159x18 mm + 31 mm when flush mounted.


Technical data	
Inputs	
power supply from Bus	28 Vdc rated voltage
absorption stand-by	10 mA
max absorption operation	350 mA
operating temperature	0 °C to +40 °C
additional power supply	with 6923

Option of using additional power supply 6923 where necessary (Bus voltage at monitor terminals 1 and 2 registering < 24 Vdc)

Front panel controls

- 1) 7" TFT LCD colour monitor, 16:9 widescreen aspect ratio.
- 2) Microphone.
- 3) Speaker.

Keypa	Keypad		
1 +	2 +	Pair of buttons: - for activation of auxiliary services - intercom calls - contrast control - talk/listen volume control - ringtone volume control.	
3 +	4 +	Pair of buttons: - for activation of auxiliary services - intercom calls - brightness control - selection of tune.	
		Button: - self-start - access control mode.	
mi		Auxiliary (e.g. stair light): assigned to auxiliary service.	
		Lock release button	
*		Talk button: - communication with entrance panel - communication with other intercom devices.	
$\dot{\mathcal{Z}}$		Call ringtone muted indicator	
		Door open indicator	



Due Fili Plus video door entry systems



7200 series - video door entry units

Video door entry unit

7211 2-channel video door entry unit with 7" TFT LCD color display, flush mounting with 7249 box, white cover



7211

7200 cover

0 0 0 0 0	
■ 72SB	7200 cover with SWAROVSKI® elements. Black
■ 72SG	As above, gold
■ 72SC	As above, chrome
■ 72GD	7200 cover. Polished gold chrome
■ 72SV	As above, metallic silver
■ 72RD	As above, metallic red
■ 72GN	As above, metallic green
■ 72BZ	As above, metallic bronze
■ 72BL	As above, metallic blue
■ 72BK	As above, metallic black



■ 72SB



72SG



■ 72SC



polished gold chrome



■ 72SV metallic silver



■ 72RD metallic red



72GN metallic green



■ 72BZ metallic bronze



■ 72BL metallic blue



72BK metallic black

Accessories

■ 720A	Desk-top base for 7200 monitor, complete with 2 m of 12-conductor cable + 1 coaxial, equipped with a comb connector, white cable
7249	Flush mounting box for Wide Touch and 7200 monitors with protective cover
■ 720E	Surface mounting box for 7200







7249

■ 720E